



**UNIFIED GOVERNMENT OF WYANDOTTE COUNTY  
& KANSAS CITY, KANSAS  
PUBLIC WORKS DEPARTMENT  
PUBLIC WORKS DEPARTMENT**

701 North 7<sup>th</sup> Street  
Kansas City, KS 66101

PHONE (913) 573-5700  
FAX (913) 573-5727

**ADDENDUM NO. 2**

**STONE HAVEN STORM SEWER  
DRAINAGE IMPROVEMENTS  
PROJECT CMIP 5034  
January 20, 2017**

The following changes and amendments are made a part of the Contract Documents for **Stone Haven Storm Sewer Drainage Improvements**. All other items and conditions of the Contract Documents remain unchanged.

**ADDENDUM NO. 2 CHANGES THE FOLLOWING:**

**DRAWINGS**

**Sheet No. 4:** Revise as follows:

Add note to brace power pole located near station 11+32, 4' right. This item will be added to the Bid Form as a separate bid item.

**Sheet No. 5:** Revise as follows:

Replace 24" HDPE Riser Tee with Manhole Ring & Cover with 30" HDPE Riser Tee with Manhole Ring & Cover.

**SPECIFICATIONS**

**Replace Special Conditions:**

Replace with attached revised copy. Summary of changes as follows:

Special Conditions – Project Conditions and Requirements

Paragraph 1.07 Lawn Restoration – Reworded to meet project requirements.

Special Conditions- Measurement and Payment

Paragraph 1.06 Standard Pay Items

- Revised Item 5 to Seeding & Mulching

- Added Item 6 **Sodding**: Unit of measurement is lump sum. Partial payment shall be made on estimated percentage complete. Sodding shall include all disturbed areas indicated in the plan set and shall also include areas disturbed due to Contractor's carelessness or unauthorized use. Soil preparation, fertilization, topsoil if required, placement, and establishment are subsidiary to this item. Reference *Section- 7000 Seeding Sodding and Mulching*.
- Revised numbers 7-30 to reflect sodding addition. No change in item descriptions
- Revise numbering for item 31 to 32. Revision to Item 32 to include concrete collar and grade adjustment
- Added Item 33 **BPU Pole Bracing**: Unit of measurement is each, field count. This bid item will include all work to brace the BPU power poles during installation of the sanitary sewer main and will include coordination and compensation to BPU for the work required. Reference Special Conditions - Project Conditions and Requirements 1.14 BPU Pole Bracing.

### **CLARIFICATIONS**

1. The entire Project Manual does not need to be turned in with the bid. Responsive bidders shall include all forms and documents as described in the **Instructions and Information to Bidders**.
2. All excavations shall be unclassified. There has been no subsurface exploration as part of this project.
3. The following attachment is included with this Addendum: Plans Sheets 4 & 5 (11x17), Revised Bid Form, Revised Special Conditions, Pre-bid meeting attendees register.
4. Concrete work, curb and gutter, sidewalk, and driveway details can be located in the Unified Government Technical Provisions & Standard Drawings available online.
5. The existing pavement profile is unknown.
6. The area of the permanent erosion control blanket is approximately 38 SY. This item is considered subsidiary to Sodding. The specifications for the blanket can be located in the Unified Government Technical Provisions & Standard Drawings Section 1400 – Construction Period Pollution Prevention Sub-section 2.01 Rolled Erosion Control Products.
7. The Remove and Replace Gravel bid item and quantity refers to a portion of the project that has gravel surfacing between two residential driveways on the west side of 52<sup>nd</sup> Terrace.
8. Removal and reinstallation of fence is considered subsidiary to other contract items. Fence removal is anticipated in the following locations.
  - a. North/south 15" HDPE – Fence is outside of grading limits. It shall be contractors responsibility if construction means and methods disturb this fence. Minimum distance from pipe CL to Fence is approximately 10'.

- b. East/west 18" HDPE – Fence running parallel shall not be disturbed as it is on property line and edge of easement. The fence does cross the alignment in two locations, total easement width is 20 feet.
  - c. Anticipated fence removal and replacement is 50' near plunge pool, within grading limits.
9. 30" HDPE Riser Tee with Manhole Ring and Cover is located on a section of pipe with a slope of 8.64%. It is anticipated that this will result in the riser portion of this tee being approximately 5-6 degrees out of plumb. A fixed bend is not an ideal application for correction, therefore, it is anticipated that this margin of deflection be accounted for at joint locations, manhole ring and cover installation, and through the minimal flexibility in the riser material.

Acknowledge receipt and acceptance of this addendum by signing below and submitting this document with the Bid. Also indicate receipt of this addendum in the appropriate space on the BID FORM.

Dated at Kansas City, Kansas this **January 20, 2017**.

  
\_\_\_\_\_  
Engineer

**A COPY OF THIS ADDENDUM SHALL BE ATTACHED TO THE PROPOSAL.**

Acknowledge Receipt of Addendum by Bidder:

\_\_\_\_\_  
Signature of Bidder

\_\_\_\_\_  
Date

\_\_\_\_\_  
Title

\_\_\_\_\_  
Company Name

**Attachments:**

Revised Bid Form

Revised Plan Sheets (Sheets 4 & 5)

Pre-Bid Sign-In Sheet