PUBLIC WORKS
WATER POLLUTION CONTROL
ADMINISTRATION 50 MARKET STREET, KANSAS CITY, KANSAS 66118 (913) 573-1300

AMENDMENT NO. 2
UNIFIED GOVERNMENT OF WYANDOTTE COUNTY / KANSAS CITY, KANSAS
ENGINEERING DIVISION, PUBLIC WORKS DEPARTMENT
CSO 19 SEWER SEPARATION (PHASE 1)
PROJECT I.D. 6311

February 29, 2024

Offerors on CSO 19 SEWER SEPARATION (PHASE 1) are hereby notified that the following amendments are made to the Project's Contract Documents. Proposals to be submitted on March 6, 2024, shall conform to these amendments. This amendment adds, changes, or clarifies the following:

AMENDMENTS TO THE CONTRACT SPECIFICATIONS:

1. GENERAL CONDITIONS:

A. Page 4: Replace paragraph 3.3 with the following:
"Prior to the commencement of Work, the Contractor shall submit to the Engineer/Architect for its review a preliminary cash flow schedule (graphic or tabular display) that indicates the anticipated value of work to be invoiced on a monthly basis through project completion. The cash flow schedule is for planning purposes of the Owner, only. Contractor's cash flow schedule will be acceptable to Engineer/Architect if it provides a reasonable allocation of the Contract Price over the Contract Time. Such acceptance will not impose on Engineer/Architect responsibility for the progress schedule, for sequencing, scheduling, or progress of the Work nor interfere with or relieve Contractor from Contractor's full responsibility therefor."

2. SPECIAL CONDITIONS:

A. Page 1: Regarding paragraph D, remove and replace the new paragraph at the end of Paragraph 1101.5 with the following:
"Unified Government permits that may be required for construction area: right-of-way use permit, haul permit, land disturbance permit, street closure permit, and building permit."

B. Page 1: Add the following as paragraph F:
"Pertaining to section 2101.3, Permits, of the Technical Provisions, add the following new paragraph at the end of paragraph 2101.3:
'Unified Government permits that may be required for construction area: right-of-way use permit, haul permit, land disturbance permit, street closure permit, and building permit.' "

3. BID:

A. Delete the Bid section in its entirety and replace with the Bid section, Revision 2, dated February 29, 2024, attached to this Amendment No. 2.

4. TECHNICAL SPECIFICATION SECTION 1400 – PROJECT INTERNAL TELEVISION INSPECTION:

C. Remove the "Pre-construction CCTV List" as attached to Amendment No. 1 and replace with "Pre-construction CCTV List", Revision 1, dated February 29, 2024, into this section.

<u>AMENDMENTS TO CONTRACT DRAWINGS:</u>

1. DRAWING NO. C002 – INDEX:

A. Remove Drawing C502 – Mechanical Pretreatment Detail I NSBB-1020

B. Insert Drawing REF015 – Reference Drawing 15

2. DRAWING NO. C113 – STORM SEWER PLAN AND PROFILE LINE 5 STA 0+00 TO STA 3+20:

A. Plan View: Revise the callout for 000-001-PRT by removing "(See Detail 1 DWG C502)" and replacing with "(See Note 2)"

B. Profile View: Revise as follows:

1. Change the invert out of 000-001-PRT from '42" INV OUT 835.66 N' to '42" INV OUT 836.04 N'
2. Change the invert in to 000-001-FCS from '42" INV IN 835.60 S' to '42" INV OUT 835.96 S'
3. Change the invert out of 000-001-FCS from '42" INV OUT 835.40 N' to '42" INV OUT 835.76 N'

C. Notes: Add the following as Note 2:
"Mechanical Pretreatment Structure shall be per DWG REF015 or approved equal. Contractor shall field grout access hatches to meet finished grade."

3. DRAWING NO. C115 – STORM SEWER PLAN AND PROFILE LINE 5A AND LINE 5B AND LINE 5C:

A. Remove Drawing C115 and replace with Drawing C115, Revision 1, dated February 29, 2024, attached to this Amendment No. 2.

4. DRAWING NO. REF015 – REFERENCE DRAWING 15:

A. Insert Drawing REF015 – Reference Drawing 15, attached to this Amendment No. 2.

5. DRAWING NO. C305 – INTERSECTION PLAN N 11TH ST AND MINNESOTA AVE N 11TH ST AND STATE AVE:

A. Keyed Notes: Remove and replace keyed note 6 with the following:
"Remove and relocate ped pole (by others). Contractor shall coordinate ped pole removal and replacement with BPU."

CLARIFICATIONS:

1. QUESTIONS:

A. Wage Rate Determination is attached.

B. Amendments must be acknowledged on the Bid Form.

C. A copy of the revised Bid section is attached. The Bid Form was revised per this Amendment No. 2 to change estimated quantity of Item B-1: Pre-Construction CCTV and Item C-7: Abandon Pipe In-Place, Fill with Flowable Fill. The bidder shall utilize the Bid section attached to this Amendment No. 2 to submit a bid.

D. A revised list of assets for Pre-Construction CCTV (Item B-1) is attached.

E. Substitutions shall be per Supplemental General Conditions paragraph F.

F. The Nyloplast Drain Basin and Note 2 on Drawing No. C115 – Storm Sewer Plan and Profile Line 5A and Line 5B and Line 5C have been removed. The existing grate inlet #5723 shall be reused. See attached Drawing No. C115 – Storm Sewer Plan and Profile Line 5A and Line 5B and Line 5C, Revision 1, dated February 29, 2024.

G. The ped pole on Drawing No. C305 – Intersection Plan N 11th St and Minnesota Ave N 11th St and State Ave shall be removed and relocated by others. Contractor shall coordinate ped pole removal and replacement with BPU. Drawing No. C305 – Intersection Plan N 11th St and Minnesota Ave N 11th St and State Ave was revised with this Amendment No. 2.

There are no further changes to CSO 19 SEWER SEPARATION (PHASE 1) at this time.

Acknowledge receipt and acceptance of this Amendment No. 2 in the appropriate space provided on the BID form.

Attachments: Wage Rate Determination
Bid Section, Revision 2
Pre-Construction CCTV List, Revision 1
Drawing C115, Revision 1
Drawing REF015